


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Edwards County, Sec. 35 Twp. 25 Rge. 16 ~~XX~~ (W)
Location as "NE/CNW/SW" or footage from lines NE NW
Lease Owner Wichita Iron & Metals Corp., Inc.
Lease Name Mayhew Well No. 1
Office Address Box 13021 - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 2-7-58 19
Application for plugging filed 3-27-67 19
Application for plugging approved 4-3-67 19
Plugging commenced 4-14 19 67
Plugging completed 4-19 19 67
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Kinderhook Depth to top 4365 Bottom 4399 Total Depth of Well 4410 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2	4410	3383
				8-5/8	388'	--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand from 4410' to 3860', ran 5 sacks cement from 3860' to 3830'.

Set plug at 300', rock from 300' to 290', ran 5 sacks cement, bailed out water, ran 20 sacks of cement from 290' to 210', mudded from 210' to 35', rock and 10 sacks cement from 35' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 1967
5-1-67

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn & Smith Pipe ~~Fixing~~ Pulling Co.
Address Box 156, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Ray Stekoll (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. WICHITA IRON & METALS CORP., INC.

(Signature) By: Ray Stekoll
Ray Stekoll
Box 13021, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of April, 19 67

Evelyn V. North
Evelyn V. North Notary Public.

My commission expires December 22, 1970


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- L. C. SMITHERMAN
 Farm- Mayhew No. 1

SEC. 35 T. 25 R. 16W
 NE NE NW

Total Depth. 4410'
 Comm. 1-24-58 Comp. 2-7-58
 Shot or Treated.
 Contractor. Lauck Drlg. Co.
 Issued. 3-7-59

County Edwards
 KANSAS



Elevation. 2058' DJ

Production. 323 BOPD

CASING:
 8 5/8" 388' cem w/275 sx.
 5 1/2" 4410' cem w/125 sx.

Figures Indicate Bottom of Formations.

clay & sand	30
sand & shale	200
blue shale	280
sand	300
red bed & shells	388
shale & shells	410
red bed	570
sand & red bed	605
red bed, shale & shells	900
shale & shells	1045
Anhydrite	1064
shale & shells	1940
lime & shale	2375
broken (soft)	2395
cherty lime	2415
lime & shale	3435
lime & some shale	3515
lime & shale	3680
lime	3716
lime & shale	3890
lime	4215
lime & shale	4330
lime	4371
chert, shale & sand	4386
chert	4410 RTD
Total Depth	

TOPS: SCOUT	
Heebner	3725
Lansing	3880
Cherokee	4340
Conglomerate	4365
Kinderhook	4390
Kinderhook Sand	4399

RECEIVED
 STATE CORPORATION COMMISSION

MAY 1 1967

CONSERVATION DIVISION
 Wichita, Kansas