


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

*Rec'd
7-11-59*

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Edwards County, Sec. 35 Twp. 25S Rge. 16W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE SW

Lease Owner Leben Drilling, Inc.

Lease Name Gradall Well No. 1

Office Address 905 Central Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-2-59 19

Application for plugging filed 7-1-59 19

Application for plugging approved 7-1-59 19

Plugging commenced 7-1-59 19

Plugging completed 7-2-59 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4470 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	289'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug @ 240' w/ 20 sx. cement 1/4 sx. Hulls
2nd plug @ 35' w/ 10 sx. cement 1/4 sx. hulls

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address 905 Central Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Frank Hamlin

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin

905 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of July, 1959

My commission expires April 23, 1963

Juanita M. Green
Notary Public.

PLUGGING
FILE SEC. 35 T. 25 R. 16W
BOOK PAGE 50 LINE 24

DRILLER'S LOG

COMPANY:
CONTRACTOR
FARM:
LOCATION
COMMENCED:
COMPLETED:

LEBEN DRILLING, INC. &
HOUSTON PETROLEUM COMPANY
LEBEN DRILLING, INC.
GRADALL #1
C SE SW SEC. 35-25S-16W
EDWARDS COUNTY, KANSAS
6-19-59
7-2-59

0	60	Sand
60	250	Sand
250	289	Shale
289	475	Sand and Shale
475	890	Redbed and Shale
890	1045	Shale and Redbed (Anhydrite 1045)
1045	1210	Shale
1210	1550	Shale
1550	1775	Shale and Shells
1775	1990	Shale and Lime
1990	2065	Lime and Shale
2065	2450	Lime
2450	2615	Shale and Lime
2615	2705	Shale and Lime
2705	3885	Lime and Shale
3885	4180	Lime
4180	4220	Lime and Shale
4220	4375	Lime
4375	4415	Cherty Lime
4415	4420	Lime and Chert
4420	4441	Sand (Kinderhook)
4441	4470	Viola Lime
	4470	Rotary Total Depth - D & A

Set 8 5/8" surface pipe @ 289' w/ 250 sacks Sunset cement.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Gradall #1, located C SE SW of Section 35, Township 25 South, Range 16 West, Edwards County, Kansas.

Frank Hamlin
Frank Hamlin

STATE OF KANSAS }
COUNTY OF SEDGWICK) SS.

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 10th day of July, 1959.

Juanita M. Green
Juanita M. Green, Notary Public

My Commission Expires:
April 23, 1963

RECEIVED
JUL 11 1959
CONSERVATION DIVISION
Wichita, Kansas

DRILLING
FILE SEC 35 T 25 R 16W
BOOK PAGE 50 LINE 24