

15-047-20452-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 35 TWP. 25s RGE. 16w E/W
Location as in quarters or footage from lines:
C - S/2 SW SE

Locate Well
correctly on above
Section Platt.

Lease Owner Oil Producers Inc, of Kansas
Lease Name Cudney "B" #1 Well No. _____
Office Address Box 8647, Wichita, Ks. 67208
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 2/28/83
Plugging completed 3/3/83
Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom T.D. 4467'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	425'	none
				4 1/2"	4466'	2025'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Dumped 4 sacks cement on top of Baker Plug set at 4390'. Shot well at
3016', 2745', 2509', 2427', 2336', 2126', & 2017'. Pulled total of 61
joints. Plugged well with 3 hulls, 16 gel, 70 cement, 10 gel, 1 hull,
plug, & 130 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 1983

Irene Hoover
Notary Public.

My Commission expires:



RECEIVED
STATE CORPORATION COMMISSION
3-14-83
MAR 14 1983

CONSERVATION DIVISION
Wichita, Kansas