

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 35 TWP. 25S RGE. 16W ~~EW~~
Location as in quarters or footage from lines:
SW SW NE NW

Lease Owner Sterling Drilling Company and F. G. Holl
Lease Name Mayhew "D" #1-35 Well No. 1-35
Office Address P. O. Box 129, Sterling, Kansas 67579
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed December 31, 1982
Application for plugging filed December 31, 1982
Plugging commenced 8:00 AM December 31, 1982
Plugging completed 10:30 AM December 31, 1982
Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation _____ Depth to top _____ bottom T.D. 4550'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	455'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole with heavy mud.
Heavy mud plugged through open ended drill pipe;
40 sacks at 980'; 50 sacks at 490'; 10 sacks with
solid bridge; 1/2 sack Hulls and plug at 40'.
10 sacks in rathole. Used 50/50 Pozmix with
2% gel and 3% cc.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the

above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
(Address)

P. O. Box 129, Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 3rd day of January, 19 83.



Agnes D. Wurst
Notary Public.
STATE CORPORATION COMMISSION

My Commission expires: April 6, 1985

JAN 05 1983
1-5-83
CONSERVATION DIVISION
Wichita, Kansas

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - MAYHEW "D" 1-35

Located: SW SW NW, Section 35-25S-16W, Edwards County, Kansas

OWNER: F. G. Holl and Sterling Drilling Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 20, 1982

COMPLETED: December 31, 1982

TOTAL DEPTH: 4550'

LOG

0 - 281 Surface Soil and Sand
281 - 408 Shale and Sand
408 - 458 Red Bed
458 - 1040 Shale, Sand and Red Bed.
1040 - 1066 Shale
1066 - 1078 Anhydrite
1078 - 1919 Shale and Lime Stringers
1919 - 4550 Lime and Shale

CASING RECORD

Ran 11 joints 8 5/8", 23# new casing.
442.89' pipe set at 455' K.B. Cemented
with 325 sacks 60/40 Pozmix with 3% cc.
Plug down at 5:45 PM, 12-20-82, by
Howco.

Plugged.

Deviation Survey: 1° at 2986'
1 1/4° at 4550'

RECEIVED
STATE COMMISSION
JAN 05 1983
CONSERVATION DIVISION
Wichita Kansas