



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 8 1963  
 10-8-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Joe Cain of Navajo Drilling Co. has this date requested permission to plug the following described well:

Mr. Cain guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Co. & Navajo Drilling Co.

Complete Address: 6810 W. Highway 54, Wichita, Kansas

Lease Name: Green Well No. # 1

Location: NE NE SW Sec. 33 Twp. 25 Rge. 12 (E) (W) W

County Stafford Total Depth 4265 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cain was instructed to plug the well as follows:

222' of 8 5/8" surface pipe, cemented with 200 sacks,  
Fill hole with drilling mud to 240', 1st cementing plug,  
1/4 sack hulls, cement with 25 sacks. Fill hole with drill-  
ing mud to 40', 2nd cementing plug, 1/4 sack hulls, cement  
with 10 sacks to base cellar. Bridge and cement bat hole  
with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent