

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 26 1963

4-26-63

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Buck Smith of Glen and Smith has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: R. P. Nixon

Complete Address: 754 E. Wichita St. Russell, Kansas

Lease Name: Slade Well No. # 1

Location: •C S/2 SW NW Sec. 35 Twp. 25 Rge. 12 (E) (W) W

County Stafford Total Depth 4141 Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Smith was instructed to plug the well as follows:

404' of 10 3/4" surface pipe cement circulated. 4139' of 7"

long string. Plugged back to 3840'. Perferated at 3640'

to 3645'. Pushed plug to 3640' cemented with 5 sacks.

Fill hole and set plug at 225', cement with 25 sacks.

Fill hole with mud to 40', set plug and 10' rock bridge cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving  
 Conservation Division Agent