

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 12 1963
8-12-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bob Miller of Graves Drilling Co. has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Shawver Armour Inc.

Complete Address: 817 Central Bldg., Wichita, Kansas

Lease Name: McCune Well No. # 1

Location: SW NE SE Sec. 5 Twp. 25 Rge. 12 (E) (W) W

County Stafford Total Depth 4168 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

291' of 8.5/8" surface pipe, cemented with 184 sacks.
Fill hole with mud to 280', 1st cementing plug, 1/4 sack
hulls, cement with 20 sacks. Fill hole with mud to 40',
2nd cementing plug, 1/4 sack hulls, cement with 10 sacks
to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent