


State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 7 1965
7-7-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jack Dunham of Aspen Drilling Company has this date requested permission to plug the following described well:

Mr. Dunham guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Company

Complete Address: Fifth Floor, Ritz Bldg., Tulsa, Oklahoma

Lease Name: Doyle Wilson Well No. # 1

Location: NE NE Sec. 26 Twp. 25 Rge. 15 (E) (W) W

County Stafford County Total Depth 4297' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dunham was instructed to plug the well as follows:

282' of 8 5/8" surface pipe, cemented with 380 sacks. Fill hole with drilling mud to 260', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent