

1 050486

20441

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,411-0000
C NW NE, SEC. 20, T 26 S, R 17 W/E
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5028
Operator: Imperial Oil Company
Name & Address 720 4th Financial Center
Wichita, KS 67202

Lease Name Mull Well # 1-20
County Edwards 148.62
Well Total Depth 4573 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 600 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 28 Month: March Year: 19 85

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4572' - PBD 4390' Perfs at 4357-62'

1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer
2nd plug squeeze well with 3 sx hulls 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 am Day: 28 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top
of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,
10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 150 sx
cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in 200 psi

APR 04 1985
4-4-85

Remarks: Recovered 3200' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Halka Barton
(If additional description is necessary, use BACK of this form.)

INVOICED (and/or observe this plugging.)

Signed Richard W. Lacey
(TECHNICIAN)

DATE 4-9-85
NO. 7532