

1030157

20453

To: STATE CORPORATION COMMISSION

CONSERVATION DIVISION - PLUGGING SECTION C S/2 SW SW, SEC. 14, T 26 S, R 17 W  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-047-20,435-000

## TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Operator: J. D. Carroll

Name &amp; Address 501 Petroleum Building

Wichita, KS 67202

Lease Name Carroll (owwo) Well # 1

County Edwards

Well Total Depth 4545 147.72 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 342

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A 

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 18 Month: April Year: 1984

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2 set at 4544 Perfs 4538 - 42

1st plug sand back to 4490' and dump 4 sx cement on top of sand

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and release 8 5/8" rubber plug and pump an additional 150 sx cement.

Maximum pressure 250# and shut in pressure 0#

Plugging Proposal Received by Steve Clement  
(TECHNICIAN)Plugging Operations attended by Agent?: All  Part  None 

Operations Completed: Hour: 3:10 pm Day: 18 Month: April Year: 1984

ACTUAL PLUGGING REPORT 4 1/2 set at 4544' Perfs 4538-42'

1st plug sand back to 4490' and dump 4 sx cement on top of sand, 2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and release 8 5/8" rubber plug and pump an additional 150 sx cement.

Maximum pressure 250# and shut in pressure 0#

Remarks: They recovered 2738' of 4 1/2" casing. Use 60/40 Pozmix 2% gel 3% cc by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOLVED

RECEIVED

STATE CORPORATION COMMISSION

DATE 4-20-84

APR 20 1984

Signed Steve Clement  
(TECHNICIAN)

INV. NO. 1184

4-18

CONSERVATION DIVISION  
Wichita, KansasFORM CP-2/3  
Rev. 01-84