

To: 1 080098  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
1307 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 13-047-21,420-0000  
170' W & 100' S  
of C NW, SEC. 13, T 26 S, R 17 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210  
Operator: Lebsack Oil Production, Inc.  
Name  
Address P.O. Box 489  
Hays, KS 67601-0489

1420 feet from NK section line  
1150 feet from WEK section line  
Lease Name Parker Well # 1-13  
County Edwards 151.77  
Well Total Depth 4670 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 420

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ O&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sterling Drilling Company License Number 5142  
Address P.O. Box 1006, Pratt, KS 67124-1006

Company to plug at: Hour: 3 a.m. Day: 5 Month: 2 Year: 19 97

Plugging proposal received from Vaughn Thompson  
(company name) Sterling Drilling Company (phone) 316-672-9508

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1130-54'.  
1st plug at 1160' with 50 sx cement, 2nd plug at 450' with 40 sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Kevin Strube  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 4:45 a.m. Day: 5 Month: 2 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 1160' with 50 sx cement,  
2nd plug at 450' with 40 sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

2-10-97

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

I ~~XXXX~~ INVOICED hereby certify and warrant that I observe this plugging.

DATE FEB 14 1997

Signed Kevin P. Strube  
(TECHNICIAN)

INV. NO. 47575