

1030235

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C S/2SW SE, SEC. 12, T. 26 S, R. 17 W
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,911-0000
660 feet from ~~N~~ SE Corner of ~~W~~ section line
2310 feet from ~~W~~ SE Corner of ~~W~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Dresie Well # 1

Operator: Vincent Oil Corporation

County Edwards

Name & Address 125 North Market, Suite 1110

Well Total Depth 4658 151.39 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 375

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 2 Month: August Year: 19 84

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4655' Perfs 4480-90'

1st plug pump 1 sack hulls and 25 sx cement

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8"

plug and pump an additional 125 sx cement.

Plugging Proposal Received by Steve Dumont
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00 am Day: 2 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 25 sx cement, 2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 125 sx cement.

Maximum pressure 250 psi and shut in pressure 150 psi

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied

(If additional description is necessary, use BACK of this form)

(If desired, you may wish to observe this plugging.)

8-6-84
RECEIVED
STATE CORPORATION COMMISSION
AUG 06 1984
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 8-14-84

Signed Steve Dumont
(TECHNICIAN)

INV. NO. 3074