

1 080039

1-30

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,300-0000

C NW, SEC. 9, T 26 S, R 17 W/EX

3960 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Roenbaugh A Well # 2-9

Operator: Murfin Drilling Company

County Edwards 153.08

Name & Address 250 North Water, Suite 300

Well Total Depth 4710 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 295

Abandoned Oil Well Gas Well X Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 30 Month: 1 Year: 1989

Plugging proposal received from Bill Brown

(company name) Murfin Drilling Company (phone) 913-483-5371

were: 4 1/2" at 4690' PBD 4657' Perfs at 4527-50' Elevation 2133' GL

On 1/25/89 Richard Lacey was at the lease and they pumped 3 sx hulls and the water surfaced to the top. Casing was run. All plugs through tubing.

1st plug pumped 200 lbs. hulls and 40 sx cement, 2nd plug at 1138' with 50 sx cement,

3rd plug at 598' with 40 sx, 4th plug at 297' with 40 sx, 5th plug at 40' with 10 sx.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 12:10 p. Day: 30 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 40 sx cement through tubing,

2nd plug pumped 50 sx cement at 1138',

3rd plug pumped 40 sx cement at 598',

4th plug pumped 40 sx cement at 297',

5th plug pumped 10 sx cement at 40'.

RECEIVED STATE CORPORATION COMMISSION

FEB 1 1989 2-1-89

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

(old) observe this plugging.

DATE 2-3-89

Signed [Signature] (TECHNICIAN)

INV. NO. 23863