

To: 1 090226  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-28

API NUMBER 15- 047-20,353-~~000~~ SW R

C SE SW, SEC. 9, T. 26 S, R. 17 W/E  
660 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30606  
Operator: Murfin Drilling Company, Inc.  
Name & Address: 250 N. Water, Ste. 300  
Wichita, KS 67202

Lease Name Boicourt Well # 1-9  
County Edwards  
Well Total Depth 4700 152.75 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 11:45 a.m. Day: 28 Month: 10 Year: 19 92

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4671' w/175 sx cement, PBSD 4566', Perfs' at 4538-49'

1st plug sand back to 4485' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 28 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4485' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3085' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

RECEIVED  
OCT 30 1992  
DIVISION  
Wichita, Kansas

INVOLVED  
Observe this plugging.

DATE 11-16-92  
INV. NO. 36753

Signed \_\_\_\_\_ (TECHNICIAN)