

To: 1 060814
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,759-0000

C N/2 NW, SEC. 4, T 26 S, R 17 ^{W/E}

4620 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8778

Lease Name George Smith Well # 1

Operator: Midwestern Supply Co., Inc.

County Edwards 151.91

Name & Address bought from Oil Property Mgt.

Well Total Depth 4674 feet

300 Patton Road

Conductor Pipe: Size _____ feet

Great Bend, KS 67530

Surface Casing: Size 8 5/8 feet 634

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 26 Month: February Year: 19 86

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers (phone) 4635

were: 4 1/2" at 4675' CIBP at 4610 & 4535' Perfs at 4498-4500'; 4505-4509'; 4572-82'; 4638-42'

1st plug sand back to 4440' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:40 am Day: 26 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4440' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 200 psi and shut in 100 psi

Remarks: Recovered 3382' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (XXXXXX) observe this plugging.

DATE MAR 04 1986

STATE CORPORATION COMMISSION Signed Paul A. Luthi

MAR 4 1986

(TECHNICIAN)

INV. NO. 12862

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84