

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-23785-00-00
Spot: NE Sec/Twnshp/Rge: 2-26S-18E
4771 feet from S Section Line, 1125 feet from E Section Line
Lease Name: HOEPKER 1 Well #: 6
County: ALLEN Total Vertical Depth: 820 feet

Operator License No.: 0
Op Name: LANDOWNER
Address: KS

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	820		95 SX
SURF	6	20		5 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/09/2015 12:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: MIKE KEPLEY Company: Phone: (620) 431-9212

Proposed Plugging Method: Locate well, run 1' pipe to TD, circ. Cement to surface, pull 1" pipe out, top off w/cement, dig out and cut off casings.

Plugging Proposal Received By: WitnessType: PARTIAL
Date/Time Plugging Completed: 09/09/2015 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Hooked onto the 2" casing and pumped 4 BBLS of water to establish rate. Pumped 6 BBLS of cement and cottonseed hulls through the 2" casing from top to bottom. Pressured casing up to 600 psi and held. Shut in. A total of 30 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
780	790		
RECEIVED KCC DIST # 3 NOV 24 2015 CHANUTE, KS RD			

Remarks:

Plugged through: CSG

PLUGGING FEES WAIVED
LANDOWNER PLUGGED AT
THEIR OWN EXPENSE.

CKM 12/1/15

District: 03

Signed

E. C. R. S.
(TECHNICIAN)

KCC WICHITA

Form CP-2/3

NOV 30 2015

RECEIVED