

2-12-88 15-185-00467-0001
Docket #D-24,022
Drill Completion Date 1/15/54
API NUMBER 15-

1 061064
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW SE, SEC. 23, T 25 S, R 12 W/E
330 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6981
Operator: Gas Marketing, Inc.
Name & Address: Box 159
Stafford, KS 67578

Lease Name Gadberry Well # 2
County Stafford 137.48
Well Total Depth 4230 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 331

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:20 a.m. Day: 12 Month: 2 Year: 19 88

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 2360' TOC 1790' PBD 2360' Perfs at 2039-54'

1st plug sand back to 1980' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 5 sx hulls, 15 sx gel, 25 sx cement, 10 sx gel, 1 sx hulls and 125 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 12 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 1980' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 5 sx hulls, 15 sx gel, 25 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1731' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1988 2-17-88

INVOICED (div. expense) observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 2-18-88

INV. NO. 19892

2+12