

SEP 8 1987

1 070406

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,104 - 0000

SW SE, SEC. 23, T 25 S, R 12 W/E

660 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6981

Lease Name Gadbury Well # 1

Operator: Gas Marketing Inc.

County Stafford 130.49

Name &

Address Box 159

Well Total Depth 4015 feet

Stafford, KS 67578

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 8 Month: 9 Year: 1987

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4015' Open hole

1st plug sand back to 3960' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 p.m. Day: 8 Month: 9 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 3960' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 130 sx cement.

STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in 300 psi.

SEP 10 1987

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1740' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form)

9-10-87

INVOICED observe this plugging.

Signed Dan Goodrow  
(TECHNICIAN)

DATE SEP 11 1987

INV. NO. 18079