

1080302

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-23,099-0000  
NE NE SE SEC. 23, T 25 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HELMER WELL # 1

TECHNICIAN'S PLUGGING REPORT

*4/15*

COUNTY STAFFORD 130.46

OPERATOR LICENSE # 31691

WELL TOTAL DEPTH 4014 FEET

OPERATOR: CORAL COAST PETROLEUM, LC PRODUCTION CSG: SIZE        " FEET

NAME AND ADDRESS 200 E 1ST, #001 SURFACE CASING: SIZE 8 5/8" @ 244' WITH        SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL        GAS WELL        INPUT WELL        SWD WELL        D/A X

OTHER WELL AS HEREINAFTER INDICATED       

PLUGGING CONTRACTOR MALLARD JV INC LICENSE NUMBER 4958

ADDRESS PO BOX 905, MCPHERSON, KS 67460

COMPANY TO PLUG AT: HOUR: 10:45 AM DAY: 15 MONTH: 04 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM CAROL

(COMPANY NAME) MALLARD JV INC (PHONE) 316-241-5640

RECEIVED  
STATE CORPORATION COMMISSION

WERE:       

APR 28 2000

1ST PLUG AT 700' WITH 50 SX CEMENT. 2ND PLUG AT 260' WITH 50 SX CEMENT.

CONSERVATION DIVISION  
Wichita, Kansas

3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL        PART        NONE X

OPERATIONS COMPLETED: HOUR: 12:10 PM DAY: 15 MONTH: 04 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 700' WITH 50 SX CEMENT. 2ND PLUG AT 260' WITH 50 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 3/4# FLO SEAL BY ACID SERVICES.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING. 5/1/00

INVOICED  
DATE 5/1/00 SIGNED [Signature]  
06/650

[Signature]  
(TECHNICIAN)

FORM CP-2/3

[Signature]  
R