

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,919 - 0000

SW NE SE, Sec. 28, T 25 S, R 12 W/E

1650 feet from N/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Letholt Well # 1-28

Operator: Texas Energies, Inc.

County Stafford

Name & P. O. Box 947

Address Pratt, KS 67124

Well Total Depth 4230 feet 137.48

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 370

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Wheatstate Oilfield Services License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 8:00 am Day: 24 Month: April Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Steve Fellers

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 4195 with 40 sx cement

2nd plug at 750' with 50 sx cement

3rd plug at 400 with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement. Plug water well with 5 sx cement

Signed J. A. [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:00 pm Day: 24 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4195' with 50 sx cement, 2nd plug at 750' with 50

sx cement, 3rd plug at 400' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with

15 sx cement, and plug water well with 5 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun

RECEIVED
STATE CORPORATION COMMISSION
MAY 03 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

INVOICED

DATE 5-7-84

INV. NO. 1395

Signed J. A. [Signature] (TECHNICIAN)