

To: 1 041158  
STATE CORPORATION COMMISSION  
Wichita, State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

3-19.

TECHNICIAN'S PLUGGING REPORT

Operator License / 3911

Operator: RAMA Operating Co., Inc.

Name: P.O. Box 159

Address: Stafford, KS 67578

API NUMBER 15- 185-21,488-0000

C SW NW, SEC. 33, T 25 S, R 12 W/EX

3300 feet from S section line

4620 feet from E section line

Lease Name Clark Well / 1-33

County Stafford

Well Total Depth 4270 138.77 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 414

Abandoned Oil Well  Gas Well  Input Well  SMD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 19 Month: 3 Year: 19 96

Plugging proposal received from Richard McIntyre

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

work: 4 1/2" at 4257' w/150 sx cement, PBTD 4242', Perfs at 4050-54, 4062-65'

1st plug sand back to 4000' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

3-26-96

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12 p.m. Day: 19 Month: 3 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4000' and dumped 4 sx cement on top of sand

bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx

gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 3-28-96

INV. NO. 45164

Signed *Stephen J. Pfeifer* (TECHNICIAN)

KANSAS RECEIVED  
MAR 28 1996  
STATE CORPORATION COMMISSION