

To: 041138
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-185-22,321-0000
SW SW SE, SEC. 4, T 25 S, R 12 W/E
530 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3911
Operator: RAMA Operating Co., Inc.
Name & Address P.O. Box 159
Stafford, KS 67578

Lease Name Jenkins Well # 1
County Stafford 135.27
Well Total Depth 4162 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 4:15 p.m. Day: 11 Month: 1 Year: 19 96

Plugging proposal received from Manny Boatwright
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

logs: 5 1/2" at 3927' w/125 sx cement, PSTD 3927', Perfs at 3724-28, 3765-69, 3804-08'
1st plug sand back to 3675' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 4:45 p.m. Day: 11 Month: 1 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3670' and dumped 5 sx cement on top of sand
through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 800 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2701' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Stephan J. Bender
(TECHNICIAN)

INVOICED
DATE JAN 23 1996
INV. NO. 44699

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1996
1-17-96