

To: 1 070048
STATE CORPORATION COMMISSION 12-11
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 185-20,893-0001
SE NW SW, SEC. 4, T 25 S, R 12 WXB
1650 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 3911

Lease Name McCune Well # 4

Operator: RAMA Operating Co., Inc.

County Stafford 138.13

Name: P.O. Box 159

Well Total Depth 4250 feet

Address

Conductor Pipe: Size feet

Stafford, KS 67578

Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well Gas Well Input Well SWD Well Was D&A
Docket D-20,160, cancelled

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 4:05 p.m. Day: 11 Month: 12 Year: 19 97

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

was: 5 1/2" at 4176' w/100 sx cement, PBTD 3910', Perfs at 3772-76, 3718-22'

1st plug sand back to 3740' and dump 5 sx cement on top of sand through bailer,

2nd plug spot 5 sx gel and 50 sx cement at 700',

3rd plug spot 50 sx cement at 330',

4th plug spot 10-15 sx cement at 40-0'. 12-15-97

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5 p.m. Day: 11 Month: 12 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3670' and dumped 5 sx cement on top of sand with bailer,

2nd plug ran tubing to 700' and spotted 5 sx gel and 50 sx cement with 2 sx calcium chloride,

3rd plug pulled tubing to 330' and spotted 50 sx cement with 1 sx calcium chloride,

4th plug spotted 23 sx cement at 40'. Good circulation throughout job.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1800' of 5 1/2" casing.

INVOICED

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE DEC 17 1997

Signed [Signature] (TECHNICIAN)

INV. NO. 49727