

1 120304

9-8

29 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,924 - 0000  
50' N of  
SE SE NW, SEC. 3, T 25 S, R 12 W/4E  
3020 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Hearn Well # 1-3

Operator: Texas Energies, Inc.

County Stafford 136.50

Name & Address P.O. Box 947

Well Total Depth 4200 feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5983

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9 a.m. Day: 8 Month: 9 Year: 19 89

Plugging proposal received from Mark Stevenson

(company name) Texas Energies, Inc. (phone) 316-672-7514

were: 4 1/2" at 4188' PBD 4147' Perfs at 3950-53'

1st plug set CIBP at 3900' with 2 sx cement on top,

2nd plug pump in 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 10 a.m. Day: 8 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3900' and dump 2 sx cement on top with bailer in 4 1/2" casing,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

3 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-500 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2217' of casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 9-18-89

Signed Duane Rankin (TECHNICIAN)

INV. NO. 25910

9-8

RECEIVED  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS  
SEP 12 1989

Rankin