

15-185-01001-0001

To: 1080437  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 8-3-51  
NE NE NE, SEC. 18, T 25 S, R 12 W R  
4950 feet from S section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6283  
Operator: The Roxana Corporation  
Name & Address: P. O. Box 1850  
Great Bend, KS 67530

330 feet from E section line  
Lease Name McCune "A", Well # 1  
County Stafford  
Well Total Depth 4220 137.15 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 293

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111  
Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 25 Month: October Year: 19 85

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 4 1/2" at 4219' PBD 3980' Perfs at 3919-27'

1st plug sand back to 3870' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:30 am Day: 25 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3870' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement

Maximum pressure 700 psi and shut in 350 psi

Remarks: Recovered 2800' 4 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE NOV 4 1985  
INV. NO. 10891

RECEIVED  
STATE CORPORATION COMMISSION

Signed J. N. Metz (TECHNICIAN)  
11-1-85

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84