

1 120946

8-1

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,723-0000

SE NW SE, SEC. 18, T 25 S, R 12
1650 feet from S section 11
1650 feet from E section 11

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039
Operator: L.D. Drilling, Inc.
Name:
Address: RR 1, Box 183B
Great Bend, KS 67530

Lease Name Bunyan Well # 1
County Stafford 139.75
Well Total Depth 4300 ft
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 243

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525-0231

Company to plug at: Hour: 10:45 a.m. Day: 1 Month: 8 Year: 19 94

Plugging proposal received from Art Strube
(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

logs: 5 1/2" at 4300' w/175 sx cement, PBSD 4273', Perfs at 4026-33, 3858-66, 3746-52, 3622-30'
1st plug sand back to 3570' and dump 5 sx cement on top of sand through bailer,
2nd plug pump in 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12:30 p.m. Day: 1 Month: 8 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3570' and dumped 5 sx cement on
top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 15 sx gel, 50 sx cement, 5
sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Pumping pressure 0-500 psi and shut in 100 psi.

RECEIVED
KANSAS CORPORATION COMMISSION
8-8-94
AUG 08 1994

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1900' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)
I did observe this plugging.

INVOICED

DATE 8-26-94
INV. NO. 41025

Signed Duane Rankin
(TECHNICIAN)

CONSERVATION DIVISION
WICHITA, KS