

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-19694-00-00

Spot: SESWNWSW

Sec/Twnshp/Rge: 21-30S-16E

1350 feet from S Section Line, 4640 feet from E Section Line

Lease Name: FEE

Well #: 5

County: WILSON

Total Vertical Depth: 824 feet

Operator License No.: 3830

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	824		100 SX
SURF	6	50		10 SX

Op Name: A X & P, INC.

Address: PO BOX 1176

INDEPENDENCE, KS 67301

Well Type: EOR

UIC Docket No: E09937.85

Date/Time to Plug: 08/21/2015 10:00 AM

Plug Co. License No.: 33969

Plug Co. Name: HOUSEL, RICK DBA RICK'S WELL SERVICE

Proposal Rcvd. from: J J HANKE

Company: A X & P, INC

Phone: (620) 325-5212

Proposed
Plugging
Method:

Establish injectivity. Bullsqueeze w 25 sx portland cement, 2% gel mix. Add cornhusks after initial squeeze. If no injectivity, RIH 1"pipe to 820ft and circulate cement slurry to surface.. POH 1"pipe and top off well w. cement.

Plugging Proposal Received By: ALAN DUNNING

WitnessType: PARTIAL

Date/Time Plugging Completed: 08/21/2015 10:00 AM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

The wellhead was hooked onto and pumped full of cement by squeezing. The well was then shut in with 800 psi. A total of 25 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
790	808		

RECEIVED
KCC DIST # 3
NOV 20 2015
CHANUTE, KS

AD

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)

CKM 12/2/15