

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-00076-00-03
Spot: SENE Sec/Twnshp/Rge: 4-17S-27W
3266 feet from S Section Line, 678 feet from E Section Line
Lease Name: LEIGHTON A Well #: 2
County: LANE Total Vertical Depth: 4350 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 2030 | | |
| PROD | 4.5 | 4320 | 0 | WITH 245 SX CMT |
| SURF | 8.625 | 337 | | WITH 220 SX CMT |

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 10/29/2015 12:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JASON SCHULER Company: ABERCROMBIE ENERGY Phone: (620) 793-8186

Proposed Plugging Method: RUN TBG TO 1800' & CIRCULATE CMT WITH HULLS. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/29/2015 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

THE WELL WAS PREVIOUSLY CEMENTED FROM 1807' TO 0' WITH 4 SQUEEZE JOBS USING A TOTAL OF 720 SX CMT. TAGGED FILL IN CASING AT 1615'. FILL 4 1/2" CASING WITH CMT FROM 1595' TO 0' IN 2 STAGES USING 120 SX CMT & 200# HULLS. TOOH WITH TBG & TOP OFF WITH 10 SX CMT. ATTEMPT TO PUMP CMT DOWN ANNULUS. COULD NOT. HAVE CMT AT BRADEN HEAD.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4192 | 4199 | | |
| 1688 | 1813 | | |

KCC WICHITA
NOV 23 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed Ken Jehlik (TECHNICIAN)

12/2/15 ckm

RECEIVED
NOV - 4 2015
KCC DODGE CITY