

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21471-00-00
Spot: N2NWNE Sec/Twnshp/Rge: 7-28S-17W
5002 feet from S Section Line, 1989 feet from E Section Line
Lease Name: MCELWAIN Well #: 1 B
County: KIOWA Total Vertical Depth: 4885 feet

Operator License No.: 6926
Op Name: ADVANTAGE RESOURCES, INC.
Address: 1775 SHERMAN ST STE 1700
DENVER, CO 80203

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4684		WITH 2 SX CMT
PROD	4.5	4884	2438	WITH 210 SX CMT
SURF	8.625	509		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/05/2015 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: NATHAN WOOD Company: COPELAND ACID & CEMENT Phone: (620) 546-5767

Proposed Plugging Method: PLUG AT 1160' WITH 15 SX GEL & 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: PARTIAL
Date/Time Plugging Completed: 11/05/2015 5:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4684' WITH 2 SX CMT. SANDED TO 4140' WITH 4 SX CMT. 1ST PLUG AT 1150' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 540' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4756	4768		
4734	4754		
4192	4196		

KCC WICHITA
NOV 23 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT

Plugged through: CSG

12/2/15 CKM

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
NOV 18 2015
KCC DODGE CITY