

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-20465-00-00
Spot: W2NW Sec/Twnshp/Rge: 33-34S-43W
3948 feet from S Section Line, 4564 feet from E Section Line
Lease Name: LINSCOTT A Well #: 4
County: MORTON Total Vertical Depth: 1388 feet

Operator License No.: 33136
Op Name: ANADARKO E & P ONSHORE LLC
Address: PO BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1337	0	WITH 450 SX CMT
SURF	8.625	373		WITH 160 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/03/2015 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PUMP 100 SX CMT WITH 100# HULLS IN THE FIRST 25 SX CMT. TIE ONTO ANNULUS & PUMP 10-50 SX CMT. PRESSURE TO 300#.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/03/2015 10:30 AM KCC Agent: WADE KLAUS

Actual Plugging Report:

PUMPED 110 SX CMT WITH 50# HULLS IN THE FIRST 25 SX CMT. TIED ONTO ANNULUS & PUMPED 10 SX CMT. PRESSURED TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
1234	1240		

KCC WICHITA
NOV 23 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

ckm2/2/15

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
NOV 13 2015
KCC DODGE CITY