

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-069-20472-00-00
Spot: SESWNWNE Sec/Twnshp/Rge: 19-25S-30W
1170 feet from N Section Line, 2149 feet from E Section Line
Lease Name: XPO-RENICK Well #: 1-19A
County: GRAY Total Vertical Depth: 5010 feet

Operator License No.: 33989
Op Name: BENGALIA LAND AND CATTLE COMP
Address: PO BOX 521008
TULSA, OK 74152

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|-----------------|
| CIBP | | 4800 | | WITH 2 SX CMT |
| PROD | 5.5 | 4975 | 0 | WITH 320 SX CMT |
| SURF | | 1800 | | WITH 590 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2015 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: EARL OCHAMPAUGH Company: BENGALIA Phone: (620) 272-0861

Proposed Plugging Method: CIBP @ 4800' WITH 2 SX CMT. PERFORATE AT 1875'. SPOT 50 SX CMT WITH 50# HULLS IN LAST 25 SX CMT. PERFORATE AT 1100'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2015 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4800' WITH 2 SX CMT. LOAD & TEST CASING TO 500#. HOLDING. PERFORATE 4 HOLES AT 1875'. INJECTION RATE THROUGH PERFS 2 1/2 BPM AT 100 PSI. PUMP 25 SX CMT, 50# HULLS THEN 25 SX CMT. DISPLACE TO 1640' LEAVING 25 SX CMT INSIDE THE 5 1/2" & 25 SX CMT OUTSIDE THE 5 1/2" CASING. PRESSURE TO 400#. PERFORATE 4 HOLES AT 1100'. CIRCULATE CMT TO SURFACE USING 268 SX CMT LEAVING THE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4862 | 4870 | | |

KCC WICHITA
NOV 23 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed

[Signature]
(TECHNICIAN)

CKM 12/2/15

RECEIVED
NOV - 4 2015
KCC DODGE CITY