

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-22382-00-00
Spot: NENENENE Sec/Twnshp/Rge: 1-20S-30W
95 feet from N Section Line, 81 feet from E Section Line
Lease Name: FRONTIER UNIT Well #: 1
County: LANE Total Vertical Depth: 4747 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		2230		CEMENTED WITH 200 SX CMT. 15 SX CMT CIRCULATED TO PIT.
PROD	4.5	4742		CEMENTED WITH 200 SX CMT
SURF	8.625	222		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/10/2015 2:00 PM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT Phone: (620) 793-5100

Proposed Plugging Method: BULL HEAD 50 SX CMT & 200# HULLS. MUD SPACER TO 2230' & CMT TO 0'. CHECK BACKSIDE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2015 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 50 SX CMT WITH 200# HULLS TO 4625'. PUMP 22 BBL SPACER BACK TO 2700'. PUMP 175 SX CMT FROM 2700' TO 0'. PRESSURE TO 400#. HOLDING. PUMP 5 SX CMT DOWN THE ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
4620	4625		
4533	4537		
4509	4512		

KCC WICHITA
NOV 23 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed

[Signature]
512

(TECHNICIAN)

CKM 12/2/15

RECEIVED
NOV 16 2015
KCC DODGE CITY