

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-25504-00-00  
Spot: N2N2NWSW Sec/Twnshp/Rge: 7-30S-17E  
2310 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: JOHN HEAD Well #: 3  
County: WILSON Total Vertical Depth: 801 feet

Operator License No.: 34769  
Op Name: CHEROKEENRG LLC  
Address: P.O. BOX 111 112 SOUTH 5TH STREET  
NEODESHA, KS 66757

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	801		126 SX
SURF	8.625	23		4 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/13/2015 12:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: PAM GRAVES Company: CHEEROKEE NRG LLC Phone: (620) 432-1840

Proposed Plugging Method: Run 1" to bottom, gel hole, spot 50' cement plug, pull up to 500', spot 50' cement plug, pull up to 225', cement to surface, pull tubing out and top off cement. Cut wellhead off below ground level and restore location.

Plugging Proposal Received By: JOHN ALMOND WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/13/2015 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2" spear hung up in hole at 391 ft by prior contractor. Therefore the tubing was perforated at 391 ft. A 1" cement string was then lowered to 391 ft inside the tubing. 84 sacks of cement were pumped. The 1" cement string was removed and the well was topped off with 6 sacks of cement. A 4.5" swedge was then installed and 12 sacks of cement pumped. The well was pressured to 350 psi and held. A total of 102 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
631	639		
616	624		

RECEIVED  
KCC DIST #3  
NOV 13 2015  
CHANUTE, KS

AD

Remarks:  
Plugged through: TBG

CKM 12/2/15

District: 03

Signed Alan Dunning  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION  
NOV 20 2015  
CONSERVATION DIVISION  
WICHITA, KS