

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20532-00-00
Spot: N2SW Sec/Twnshp/Rge: 30-24S-40W
1978 feet from S Section Line, 4078 feet from E Section Line
Lease Name: WOOD Well #: 4A-30
County: HAMILTON Total Vertical Depth: 2400 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2400	0	WITH 650 SX CMT
SURF	8.625	338		WITH 180 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/09/2015 12:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/09/2015 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL CASING WITH CMT FROM 2378' TO 0' USING 200# HULLS & 150 SX CMT.
PRESSURED TO 350#. HOLDING. PUMP 20 SX CMT DOWN THE ANNULUS TO 250#.
HOLDING. TOP OFF 4 1/2" CASING WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2370	2378		

KCC WICHITA
NOV 23 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
SA

(TECHNICIAN)

RECEIVED
NOV 16 2015
KCC DODGE CITY