

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-025-21476-00-00
Spot: SWNESENW Sec/Twnshp/Rge: 10-34S-21W
1950 feet from N Section Line, 2025 feet from W Section Line
Lease Name: HARPER Well #: 1
County: CLARK Total Vertical Depth: 5560 feet

Operator License No.: 31691
Op Name: CORAL COAST PETROLEUM, L.C.
Address: 8100 E 22ND ST N BLDG 600, STE R
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5345		WITH 2 SX CMT
COND	20	76		WITH 20 SX CMT
PROD	5.5	5559	2600	WITH 175 SX CMT
SURF	8.625	647		WITH 795 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/21/2015 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVID PAULY Company: CORAL COAST PETROLEUM Phone: (316) 250-2045

Proposed Plugging Method: Set CIBP @ 5345' spot 2 sx. cement on plug. Pull casing. TIH w/ 2-3/8" tbg. to 970' spot 50 sx. . Spot 50 sx. 680'. Spot 20 sx. 60' to surface.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 10/21/2015 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 5345' WITH 2 SX CMT. 1ST PLUG AT 983' WITH 12 SX GEL & 50 SX CMT.
2ND PLUG AT 698' WITH 50 SX CMT. 3RD PLUG AT 63' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5392	5398		

KCC WICHITA
NOV 23 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed *Michael Maier*
(TECHNICIAN)

CKM
12/2/15

RECEIVED
NOV - 4 2015
KCC DODGE CITY

JTA