

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-19013-00-02
Spot: NWNWNW Sec/Twnshp/Rge: 22-26S-9W
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: NUNEMAKER-REECE Well #: 1
County: RENO Total Vertical Depth: 4153 feet

Operator License No.: 35216

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 4.5 | 3996 | 175 | 175 SX |
| SURF | 8.625 | 290 | 210 | 210 SX |

Op Name: ENERGYQUEST II, LLC

Address: 4526 RESEARCH FOREST DR> SUITE 2
THE WOODLANDS, TX 77381

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 10/29/2015 12:00 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE

Company: QUALITY WELL SERVICE

Phone: (405) 656-3151

Proposed Plugging Method: AS PER KCC RULES & REGS

KCC WICHITA
DEC 01 2015
RECEIVED

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: PARTIAL

Date/Time Plugging Completed: 11/03/2015 4:00 PM

KCC Agent: B. J. HOPE

Actual Plugging Report:

TRIPPED TUBING INTO 3850 - SPOTTED 50 SX OF CEMENT. 150 LBS OF HULLS & 3% CC. TAGGED TOP OF CEMENT AT 3750'. CIRCUALTED HOLE CLEAN, PUSHED 80 BBLs OF MUD TO PIT. RUN INTO 1350' PERFORATED ALSO AT 800' AND 340'. TRIPPED TUBING INTO 1350' SPOTTED 40 SX OF CEMENT 100 LBS OF HULLS & 3% CC, TAGGED TOC @ 1200', RAN TUBING TO 800' SPOTTED 35 SX OF CEMENT 100 LBS OF HULLS & 3% CC, TAGGED AT 670', TRIPPED TUBING TO 340' CIRCUALTED TO SURFACE WITH 165 SX OF CEMENT, 50 LBS HULLS, 2% CC. CUT HEAD OFF 12" NOT 8 5/8" AS CP-1 STATED, RAN ONE INCH INTO 136' AND CIRCUALTED TO SURFACE WITH 210 SX OF CEMENT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3850 | 3860 | | |

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT ON THIS JOB. WELL PLUGGED, PAST 10 YEAR TA.

Plugged through: CSG

CKM 12/2/15

District: 02

Signed

BT Hope

(TECHNICIAN)