

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-001-29009-00-00  
Spot: W2SWSW Sec/Twnshp/Rge: 29-24S-18E  
660 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: KRAMER Well #: 1-29  
County: ALLEN Total Vertical Depth: 1200 feet

Operator License No.: 33741  
Op Name: ENERJEX KANSAS, INC.  
Address: PO BOX 45  
RANTOUL, KS 66079

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1186		183 SX
SURF	8.625	43		10 SX

Well Type: GAS UIC Docket No: Date/Time to Plug: 10/09/2014 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: JARROD HAMMOND Company: Phone: (785) 241-2228

Proposed Plugging Method: Filled with Cement from the Bottom up.

Plugging Proposal Received By: WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/09/2014 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Drilled rock and debris out of the 5.5" casing to 250'. Encountered iron. Circulated cement through the drill stem from 250' to surface. Pulled drill stem from well and hooked directly to the 5.5" casing. Pressured casing with cement to 1000 psi and shut in.

Perfs:

Top	Bot	Thru	Comments
1085	1087		SPF
840	886		SPF
818	820		SPF
713	715		SPF
702	704		SPF
620	622		SPF
293	300		SPF

RECEIVED  
KCC DIST #3  
NOV 24 2015  
CHANUTE, KS

RD

Remarks:

Plugged through: DP

District: 03

Signed

[Signature] E.C.R.S.  
(TECHNICIAN)

CKM 12/2/15

Form CP-2/3  
KCC WICHITA  
NOV 30 2015  
RECEIVED