

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-02369-00-00
Spot: NENENE Sec/Twnshp/Rge: 31-11S-20W
330 feet from N Section Line, 330 feet from E Section Line
Lease Name: CASKEY Well #: 4
County: ELLIS Total Vertical Depth: 3865 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3836		unknown amount of cement
SURF	8.625	315		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2015 11:00 AM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
Proposal Rcvd. from: BRIAN CABLE Company: WILD WEST WELL SERVICE, INC. Phone: (785) 445-2888

Proposed Plugging Method: Ordered 475 sx 60/40 pozmix 4% gel cement w/500 # hulls.
11/10/2015- Ordered 200 sx 60/40 pozmix 4% gel cement.
Squeezed at 1605' and 985'.
Stage collar 3263?
ARB open hole - Bridge plug at 3650'
Perforations: 3426' - 3430', 3599' - 3564', 3579' - 3585', 3599' - 3601', 3835' - 3838'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2015 11:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Pioneer logging perforated at 2050'. Wild West ran in hole with tubing to 3400'. Swift rigged to tubing and pumped 150 sx cement w/300 # hulls mixed in. Pulled tubing to 2000' and pumped 300 sx cement w/200 # hulls mixed in. Good circulation. No cement. 600 # lift pressure. Pulled tubing to 1000' and pumped 25 sx cement. Ran out of cement at 2:00pm. 11/10/2015- 8:30am Ran in hole and tagged cement at 760'. Swift rigged to tubing and pumped 80 sx cement to circulate cement to surface. Pulled tubing and topped off 5 1/2" casing with 15 sx cement. Hole standing full. Pumped 25 sx cement in 8 5/8" surface casing and pressured to 400 psi. Shut in pressure 400 psi.

GPS: 39.05803 -099.57623

Perfs:


Top	Bot	Thru	Comments
3835	3838		
3599	3601		
3579	3585		
3559	3564		
3426	3430		

Remarks: SWIFT CEMENTING SERVICES TICKET # 28740

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CKM 12/2/15

(M)

NOV 12 2015

KCC WICHITA

NOV 25 2015

RECEIVED