

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-063-22273-00-00  
Spot: SWNENWSW Sec/Twnshp/Rge: 25-14S-30W  
2300 feet from S Section Line, 935 feet from W Section Line  
Lease Name: KUHN Well #: 1  
County: GOVE Total Vertical Depth: 4480 feet

Operator License No.: 33922  
Op Name: MUSTANG ENERGY CORPORATION  
Address: PO BOX 1121  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		150 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/13/2015 12:00 AM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: KIRBY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE  
Date/Time Plugging Completed: 11/13/2015 10:45 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st plug @2120 w/50 sx  
2nd plug @1210 w/100 sx  
3rd plug @270 w/50 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

District: 04

Signed Richard Williams  
(TECHNICIAN)

CKM 12/2/15

CM

NOV 17 2015

KCC WICHITA Form CP-2/3

NOV 25 2015

RECEIVED