

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Gear Petroleum Company, Inc.

API NO. 15-047-21,015-0000

ADDRESS 300 Sutton Place

COUNTY Edwards

Wichita, Kansas 67202

FIELD Fatzer

**CONTACT PERSON Jim Thatcher

PROD. FORMATION

PHONE 316 265 3351

LEASE Fisher "A"

PURCHASER

WELL NO. 2-15

ADDRESS

WELL LOCATION N/2 N/2 SE/4

DRILLING Red Tiger Drilling Company-Allied Cementing

330 Ft. from North Line and

CONTRACTOR Russell, Ks. 1320

Ft. from East Line of

ADDRESS 1720 KSB Building

the SE/4 SEC. 15 TWP. 26S RGE. 17W

Wichita, Kansas 67202


WELL PLAT

PLUGGING Red Tiger Drilling Company

CONTRACTOR

ADDRESS 1720 KSB Building

Wichita, Kansas 67202



KCC
KGS.
(Office Use)

PLG ✓

TOTAL DEPTH 4,700' PBD

SPUD DATE 3/23/82 DATE COMPLETED 4/3/82

ELEV: GR 2,123' DF KB 2,128'

DRILLED WITH (ROTARY) TOOLS

Amount of surface pipe set and cemented 282.42' DV Tool Used? No

AFFIDAVIT

STATE OF Kansas, COUNTY OF Sedgwick SS, I,

Jim Thatcher OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Drlg/Prod Manager (FOR)(OF) Gear Petroleum Company, Inc.

OPERATOR OF THE Fisher "A" LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 2-15 ON


SAID LEASE HAS BEEN COMPLETED AS OF THE 3rd DAY OF April, 19 82, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Jim Thatcher

SUBSCRIBED AND SWORN BEFORE ME THIS 19th DAY OF April, 19 82



Helen L. Coyer 4-20-82

NOTARY PUBLIC RECEIVED STATE CORPORATION COMMISSION

MY COMMISSION EXPIRES April 1, 1986

**The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

CONSERVATION DIVISION Wichita, Kansas

SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION; CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand	0	287	Heebner	3863
Shale & Sand	287	527	LKC	4005
Sand & Shale	527	1955	Base LKC	4366
Shale	1955	2445	Mississippi	4531
Lime & Shale	2445	2635	Kinderhook	4553
Shale & Lime	2635	2723	Viola	4650
Lime & Shale	2723	3850		
Lime	3850	3985		
Lime & Shale	3985	4295		
Lime	4295	4388		
Lime & Shale	4388	4520		
Lime	4520	4545		
Lime & Shale	4545	4570		
Lime	4570	4656		
Lime & Shale	4656	4700		
RTD	4700			

DST #1:
4491-4520, Miss-run

DST #2:
4473-4520, Times 30/60/45/90, Rec 30' GCM, 57 MCF in 45 min., Flow Pressure 69/69-69/69, SIP 1466/1466

DST #3:
4531-4545, Times 30/60/45/90, Rec 45' GCM, Flow Pressure 24/24-39/24 SIP 1310/1470

DATE: JUN 1 1983

FROM CONFIDENTIAL

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (~~XXX~~)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	289.32'	Common	225	3% C.C., 2% Gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
--------------------------	---	---------

RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Water %	Gas-oil ratio	CFPB
---------------------------------	-----------	---------	---------------	------

Disposition of gas (vented, used on lease or sold) Perforations

JUN 1 1983

FROM CONFIDENTIAL