

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 17 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Terrel Drilling & Producing

Complete Address: Russel, Kansas

Lease Name Maskus Well No. # 1

Location C NW NW Sec. 1 Twp. 25 Rge. 25 (E) (W)

County Ford Total Depth 4850'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Terrel Drilling & Producing

Address: Russell, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 3 PM Day 14 Month 6 Year 63

The Above well was plugged as follows:

8 5/8" - 275' Circulated w/cement.

Mud 4850' to 500' Hulls, 25 Sax. cement 500' to 425'

Mud 425' to 250' Hulls, 25 Sax. cement 250' to 175'

Mud 175' to 40' Hums, 15 Sax. cement 40' to surface.

Company Pump.

I hereby certify that the above well was plugged as herein stated.

DATE 6/19/63

INV. NO. 7275-W

Signed: [Signature]  
Well Plugging Supervisor