

15-185-00272-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford

County, Sec. 23 Twp. 25S Rge. 12 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SE SW
Lease Owner National Cooperative Refinery Association
Lease Name Slade Well No. 1
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed October 28, 1953
Application for plugging filed February 15, 1956
Application for plugging approved February 16, 1956
Plugging commenced March 23, 1956
Plugging completed March 29, 1956
Reason for abandonment of well or producing formation Depletion

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production January 31, 1955
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Brundage
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4218 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	265'	None
				5 1/2"	4212'	2027'
				Hole plugged back to 3850'		
				Casing perforated 3819' to 3824'		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled the hole with sand from 3850' to 3810' and ran 5 sacks of cement. Pumped in 15 sacks of jell mud and 90 sacks of cement to fill the surface casing. Filled the hole with mud and ran 5 sacks of cement to fill to base of cellar. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Sears (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears (C. R. Sears)
305 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of April, 1956

My commission expires June 30, 1958.

C. Orville May
Notary Public.
C. Orville May

24-7368-5 3-53-20M

PLUGGING
FILE SEC 23 T 25 R 12W
BOOK PAGE 39 LINE 2

4-6-56

15-185-00272-0000

CONTRACTOR'S WELL LOG

COMPANY:	National CoOperative Refinery Association
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	SLADE #1
LOCATION:	SW SE SW, Section 23-25S-12W Stafford County, Kansas.
COMMENCED:	October 1, 1953
COMPLETED:	October 14, 1953

0	120	Sand and gravel
120	140	Blue clay
140	655	Red bed
655	675	Anhydrite
675	1415	Shale & shells
1415	2520	Lime & shale
2520	2812	Shale & lime shells
2812	3580	Shale & lime
3580	3620	Lime
3620	3774	Lime & shale
3774	3818	Lime
3818	3905	lime & shale
3905	3936	Lime & shale & chert shells
3936	3951	Marm. chert
3951	3974	Cong.
3974	4014	Shale
4014	4021	Viola
4021	4048	Viola lime
4048	4105	Viola
4105	4115	Shale
4115	4143	Cherty lime & shale
4143	4177	Simpson
4177	4218	Shale
	4218	Rotary Total Depth

Set 8-5/8" surface casing at 265' with 225 sacks of cement & 2 sacks calcium chloride.

Set 8-5/8" casing at 4212' with 200 sacks cement.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the SLADE #1, SW SE SW, Section 23-25S-12W, Stafford County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 20th day of October, 1953.

Alma E. Rasmussen
 Notary Public

My commission expires July 16, 1955.

