

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-00467-0006

LEASE NAME Gadberry

WELL NUMBER #2 SWD

         Ft. from S Section Line

         Ft. from E Section Line  
SW SW SE

SEC. 23 TWP. 25 RGE. 12W (E) or (W)

COUNTY Stafford

Date Well Completed         

Plugging Commenced 2-08-88

Plugging Completed 2-12-88

LEASE OPERATOR Gas Marketing, Inc.

ADDRESS Box 159  
Stafford, Kansas 67578

PHONE#(316) 234-5191 OPERATORS LICENSE NO. 6981

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4230'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"	331'	none
				5-1/2"	2360'	1731'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

Plugged off bottom with sand to 1980' and 5 sacks cement. Shot pipe @1731', pulled a total of 56 joints of 5-1/2" casing. Plugged surface with 5 hulls, 15 gel, 25 cement, 10 gel, 1 hull and 125 cement, 60/40 pos, 6% gel.  
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters hereinafter contained and the log of the above-described well as filed that the same are true and correct, so help me, God.

(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 23rd. day of February, 19 88

James Hoover  
Notary Public

My Commission Expires:

