


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-185-00415-0000

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County. Sec. 32 Twp. 25 Rge. (E) 12 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SW
Lease Owner Phillips Petroleum Company
Lease Name Copenhaver Well No. 1
Office Address Box 779 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed August 11, 19 51
Application for plugging filed August 13, 19 51
Application for plugging approved August 14, 19 51
Plugging commenced August 15, 19 51
Plugging completed August 21, 19 51
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production Non - productive 19...
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough,
Producing formation Arbuckle Depth to top 4282 Bottom 4332 Total Depth of Well 4332 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Anhydrite	Dry	965'	1165'	8 5/8"	228'	None
L. K. C.	Dry	3621		5 1/2"	3741	2609'
Simpson	Dry	4192				
Arbuckle	Dry	4282	4332			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set.

Plugged back from 4332' to 4150' with 50 sx. cement. Set plug at 3674'.
Filled hole with mud to surface and pumped in 100 sx. cement under
pressure. Well Plugged and Abandoned at 4:00 PM 8/21/51

VED
COMMISSION

AUG 24 1951

8-24-51

WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mr. A. J. Willis
Address Box 779 - Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.
A. J. Willis (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn, on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *A. J. Willis*

Box 779 - Great Bend, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of August, 19 51.

My commission expires November 18, 1953



PLUGGING
FILE SEC 32 T 25 R 12 W
BOOK PAGE 102 LINE 29

Joseph M. Beal
Notary Public.

Formation Record

15-185-00415-0000

Lease

Copenhagen

Well No.

1

FROM	TO	Formation	REMARKS
0	65	Sand and gravel	Elevation: Ground 1879'
65	160	Sand and Shale	D.P. 1891'
160	215	Redbed and Shale	O.R.S. 1893'
215	430	Shale and Shells	
430	700	Shale and Redbed	
700	865	Shale and Shells	
865	887	Anhydrite	
887	1475	Redbed, Shale and Shells	
1475	1617	Shale and Galt	
1617	1695	Shale and Lime	
1695	1787	Shale and Shells	
1787	2090	Lime and Shale	
2090	2120	Shale	
2120	2200	Lime	
2200	2900	Lime and Shale	
2900	2925	Lime	
2925	3060	Lime and Shale	
3060	3060	Lime	
3060	3110	Lime and Shale	
3110	3331	Lime	
3331	3385	Sandy Lime	
3385	3460	Lime	Top: Heebner 3438' Toronto 3450'
3460	3655	Lime and Shale	Top: Brown Lime 3599' LKC 3622'
3655	3739	Lime	
3739	3777	Lime and Chert	
3777	3953	Lime	
3953	3988	Lime, Shale and Chert	
3988	4007	Lime and Chert	
4007	4022	Lime	Top: Mississippi 4018'
4022	4049	Chert	Top: Kinderhook 4048'
4049	4054	Chert and Shale	
4054	4115	Chert	
4115	4146	Chert and Sandy Lime	
4146	4160	Chert, Sand and Lime	
4160	4192	Chert, Lime and Shale	Top: Simpson 4172'
4192	4216	Simpson Sand	
4216	4232	Sand	
4232	4282	Shale and Lime	Top: Arbuckle 4282'
4282	4332	Lime	

ST. ... COMMISSION

AUG 24 1951 8-24-51

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 32 T 25 R 12W
BOOK PAGE 102 LINE 29