


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-185-11898-0000  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County, Sec. 35 Twp. 25S Rge. (E) 12 (W)  
Location as "NE/CNW%SW%" or footage from lines SW SE NW  
Lease Owner Musgrove Drilling Company  
Lease Name SLADE "A" Well No. 1  
Office Address 801 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed March 21, 1962 19 62  
Application for plugging filed verbally - March 20, 1962 19 62  
Application for plugging approved verbally - March 20, 1962 19 62  
Plugging commenced March 21, 1962 19 62  
Plugging completed March 21, 1962 19 62  
Reason for abandonment of well or producing formation DRY

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes.

Name of Conservation Agent who supervised plugging of this well  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4285' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	680'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole w/heavy mud to 240'.  
Set 1st Plug at 240' w/ 1/4 sk hulls & 30 sx cement.  
Filled hole w/heavy mud to 35'.  
Set 2nd plug at 35' w/ 1/4 sk hulls & 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 10 1962  
CONSERVATION DIVISION  
WICHITA, KANSAS

4-10-62

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Bowers Drilling Company, Inc.  
Address 416 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
A. L. Abercrombie (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *A. L. Abercrombie*  
801 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of April, 19 62

*Reah Joyce Hefler*  
Notary Public.

My commission expires June 16, 1963

WELLLOG

15-185-11898-0800

COMPANY: Musgrove Drilling Company  
 CONTRACTOR: Bowers Drilling Company, Inc.  
 FARM: Slade "A" #1  
 LOCATION: SW SE NW Sec. 35-25S-12W  
 Stafford County, Kansas  
 COMMENCED: 3-6-62  
 COMPLETED: 3-21-62  
 ELEVATION: 1873 KB

0	-	675	Sand & Redbed	Set 8 5/8" Suff. Csg. @680'
675	-	705	Anhydrite	w/410 sax.
705	-	1145	Shale - Redbed	
1145	-	<del>1608</del>	Shale & Shells	
1608	-	1832	Lime & Shale	
1832	-	1966	Lime	
1966	-	2273	Lime & Shale	
2273	-	2713	Shale & Lime	
2713	-	3636	Lime & Shale	
3636	-	4010	Lime	
4010	-	4114	Lime & Shale	
4114	-	4122	Viola	
4122	-	4165	Lime & Chert	
4165	-	4260	Lime	
4260	-	4285	Arbuckle	
4285	-		Total Depth	

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 13 1962

CONSERVATION DIVISION  
 Wichita, Kansas

7-13-62

LOG TOPS:

Heebner	3424	Marmaton	3937
Toronto	3436	Mississippi	4033
Douglas	3456	Viola	4106
Brown Lime	3599	Simpson	4192
Lansing	3622	Arbuckle	4258
Base K. C.	3932		

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the copy of the log of the Slade "A" #1, SW SE NW, Section 35-25S-12W, Stafford County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

*Emil E. Bowers*  
 Emil E. Bowers

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 5<sup>th</sup> day of April, 1962.

*Leah Faye Hefke*  
 Leah Faye Hefke, Notary Public

My Commission expires June 16, 1963.