


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Stafford County, Sec. 35 Twp. 25 Rge. 12 (E) (W)



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines C S/2 SW NW
Lease Owner R. P. Nixon
Lease Name Slade Well No. 1
Office Address 754 East Wichita, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed April 4 1963
Application for plugging filed April 15 1963
Application for plugging approved April 16 1963
Plugging commenced April 18 1963
Plugging completed April 22 1963
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4140 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 10 3/4 | 405' | |
| | | | | 7 " | 4139' | 3132' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 3640', run 5 sacks cement from 3640' to 3620'.
Mudded from 3620' to 225'. Rock bridge from 225' to 215',
run 25 sacks cement from 215' to 160' mudded from 160' to
40' rock, 15 sacks cement from 40' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAY 27 1963

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co. (If additional description is necessary, use BACK of this sheet)
Address Box 114, Ellinwood, Kansas

STATE OF KANSAS COUNTY OF RUSSELL, ss.
R. P. Nixon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. P. Nixon
754 East Wichita, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of May, 1963

My commission expires January 5, 1965
Ruth E. Miller
Ruth E. Miller, Notary Public.



Shields


Russell, Kansas

WELL LOG

15-185-11896-0000

Operator: R. P. Nixon
 Well: Slade #1
 Commenced: March 1, 1963
 Completed: March 16, 1963
 Contractor: Shields Drilling Co., Inc.

Well Description: S/2 SW/4 NW/4
 Sec. 35-25S-12W
 Stafford County, Kansas



CASING RECORD

| Size | Run | Pulled |
|----------|--------|-----------------|
| 10 3/4 " | 405' | Cmtd w/200 sax. |
| 7" | 4,139' | Cmtd w/200 sax. |

Elevation:
 Treatment:
 Production:
 Tops:

..... Figures Indicate Bottom of Formations

| | |
|------------------------|------------|
| Shale & sand | 405' |
| Shale, redbed & shells | 690' |
| Shale & shells | 1,190' |
| Redbed, shale & shells | 1,451' |
| Anhydrite | 1,460' |
| Shale & shells | 1,500' |
| Shale, shells & lime | 1,780' |
| Shale, lime & chert | 2,020' |
| Lime & shale | 3,210' |
| Lime | 3,340' |
| Lime & shale | 3,555' |
| Lime | 3,985' |
| Lime, shale & chert | 4,070' |
| Lime & chert | 4,140' RTD |

RECEIVED
 STATE CORPORATION COMMISSION

JUN 25 1963

CONSERVATION DIVISION
 Wichita, Kansas

NOTES

Notes