

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-185-21,924-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.) 6/89

LEASE OPERATOR Texas Energies, Inc. OPERATORS LICENSE NO. 5087
ADDRESS P.O. Box 947 Pratt, KS 67124 PHONE # (316) 672-7514
LEASE (FARM) Hearn WELL NO. 1-3 WELL LOCATION SE SE NW COUNTY Stafford
SEC. 3 TWP. 25S RGE. 12 (X) or (W) TOTAL DEPTH 4200 PLUG BACK TO 4147

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____
SURFACE CASING SIZE 8 5/8" SET AT 300 CEMENTED WITH 200 SACKS
CASING SIZE 4 1/2" SET AT 4188 CEMENTED WITH 150 SACKS
PERFORATED AT 3950-3953

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Ensure that well is dead. Drop 50' sand above the top perforation and dump 4 sxs cement on top with bailer. Freepoint and pull casing. Pump down 8 5/8" casing 400 sxs hulls, 10 sxs gel, 50 sxs 60-40 poz cement with 6% gel, 10 sxs gel, 100# hulls, 8 5/8" wiper plug and 100 sxs 60-40 poz cement with 6% gel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As soon as convenient

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mark P. Stevenson PHONE # (316) 672-7514 RECEIVED
ADDRESS P.O. Box 947 Pratt, KS 67124 JUN 23 1989
PLUGGING CONTRACTOR Texas Energies, Inc. LICENSE NO. 5087 6-23-89
ADDRESS P.O. Box 947 Pratt, KS 67124 PHONE # (316) 672-7514 CONSERVATION DIVISION
Wichita, Kansas

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Mark P. Stevenson
(Operator or Agent)

ORIGINAL

DATE: June 21, 1989

State of Kansas



Kansas Corporation Commission

JOHN HAYDEN
ALVIN D. HENLEY
MICHAEL KOWALEWSKI
MARCELEE WRIGHT
JUDITH MCCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

THIS NOTICE

SEP 26 1989

EXPIRES

June 26, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3230

Texas Energies, Inc.
P. O. Box 947
Pratt, KS 67124

Hearn #1-3
50'N SE SE NW
Sec. 03-25S-12W
Stafford County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760