


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-185-00517-0000

NORTH



Locate well correctly on above
Section Plat

STAFFORD County. Sec. 17 Twp. 25 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Aurora Gasoline Company, Etal
Lease Name Mc Cune Well No. 1
Office Address 1107 Union National Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 9 19 58
Application for plugging filed " 19 "
Application for plugging approved " 19 "
Plugging commenced " 19 "
Plugging completed " 19 "
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, 222 So. Main, St. John, Kansas
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 4221 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	0	260	8 5/8"	255	None
See Attached Log						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud from 4221' to 250': Permanent bridge at 250' with 15 Sacks of cement:

Mud from 250' to 50': Bridge at 50' with 10 Sacks of cement cap.

STAFFORD COUNTY, KANSAS

MAY 22 1958

CONSERVATION DIVISION
Wichita, Kansas

5-22-58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rex & Morris Drilling Company
Address Box 334, El Dorado, Kansas

STATE OF Kansas COUNTY OF Butler, ss.
C. E. McClure (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. McClure

Box 334, El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of May 1958

Winifred E. Cruik
Winifred E. Cruik
Notary Public.

My commission expires July 23, 1960

PLUGGING
FILE SEC 17 T. 25 R. 12
BOOK PAGE 100 LINE 26

15-185-00517-0000
Elevation 1893 RB
1890 DF

McCUNE WELL # 1

AURORA GASOLINE CO. & REX & MORRIS

Total Depth - 4221
Contractor - Rex & Morris Drilling Co.
Commenced - 4-29-58
Completed - 5-9-58
Initial Production - D & A

Location - SW SW NE
Section - 17-25S-12W
Stafford County, Kansas.
8 5/8" @ 255' w/ 275 sacks

FORMATION	DEPTH
Surface Hole	260
Shale and Red Bed	880
Shale & Shells	1610
Lime & Shale	2300
Shale & Lime	2820
Lime & Shale	3173
Lime	3280
Lime & Shale	3600
Lime	3963
Conglomerate	3995
Lime & Shale	4038
Lime (Cherty)	4080
Lime	4137
Lime & Shale	4181
Lime T.D.	4221

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

By *Paul M. Plouffe*

Title Geologist

STATE OF KANSAS)
) SS.
COUNTY OF BUTLER)

Subscribed and sworn to before me, a Notary Public, this 21 day of May, 1958.

Winifred E. Cruit
Winifred E. Cruit - Notary Public

My commission expires:
July 23, 1960.

RECEIVED
STATE OF KANSAS COMMISSIONS

MAY 22 1958 5-22-58

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE - SEC 17 T 25 R 12W
BOOK PAGE 100 LINE 26