

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Stafford County. Sec. ²⁶23 Twp. ^{25S}21S Rge. 15W (E) (W)
 Location as "NE/CNWxSWx" or footage from lines NE NE
 Lease Owner National Associated Petroleum Company
 Lease Name Wilson Well No. 1
 Office Address 5th Floor, Ritz Building, Tulsa, Oklahoma
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed June 6 19 65
 Application for plugging filed June 6 19 65
 Application for plugging approved June 6 19 65
 Plugging commenced June 6 19 65
 Plugging completed June 6 19 65
 Reason for abandonment of well or producing formation Dry Hole - not commercial.
 If a producing well is abandoned, date of last production _____ 19 ____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4297 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Wooden Plug @ 265, 1/4 sack hulls, 25 sacks cement, mud to 40 feet.
Wooden Plug, 1/4 sack hulls, 10 sacks cement, 2 sacks cement in rat hole.

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 7 1965
 7-7-65
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aspen Drilling Company
 Address P. O. Box 783, Great Bend, Kansas

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.
Joe E. McGarran (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe E. McGarran
Fifth Floor, Ritz Building, Tulsa, Oklahoma
 (Address)

Subscribed and sworn to before me this 6th day of July, 19 65

My commission expires February 21, 1969
Maxine D. Provine Notary Public.

15-185-30052-0000

D R I L L E R S L O G

#1 Wilson

CASING RECORD: 12 Jts. 8-5/8" COMPANY: National Associated Petroleum Co. DESCRIPTION: NE NE Section 26-T25S-R15W Stafford County, Kansas

TOTAL DEPTH: 4297' CONTRACTOR: Aspen Drilling Co.

COMMENCED: May 26, 1965 ELEVATION: 2008 K.B. 2006 D.F. 2003 GR.

COMPLETED: June 6, 1965

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks:</u>
Sand	0	200	Spudded at 4:00 p.m. 5-26-65. Ran 12 Jts.
Red Bed & Shale	200	284	8-5/8" used surface casing to 282 ft.
Red Bed	284	938	Used 275 sacks cement, 3% CA.CL. Plug down
Anhydrite	938	954	at 10:45 p.m. Cement did not circulate.
Red Bed & Shale	954	1240	Used 50 sacks cement with 2 in. pipe to
Shale	1240	1625	fill up around top 30 ft. surface casing.
Shale - Shells	1625	1850	
Lime & Shale	1850	2800	<u>DST #1</u> 3955' to 3970' Open hr. Weak blow
Shale & Lime	2800	3035	throughout. Recovered 40' oil specked mud.
Lime & Shale	3035	3798	ISIP 1412#/30 min. FSIP 1285#/30 min.
Lime	3798	4297	IFP 30# FFP 51#. IHYD 2139 FHYD 2127.
	<u>Sample Tops</u>		<u>DST #2</u> 4242' to 4265'. Open 1 hr. Strong
Heebner	3653	-1645	blow throughout. 2700' gas in pipe. 50'
Lansing	3822	-1814	gas cut mud. ISIP 464#/30 min. FSIP
Mississippian	4246	-2238	590#/30 min. IFP 27# FFP 48#. IHYD 2306
			FHYD 2294.
			<u>DST #3</u> 4265' to 4297'. Open 1 hr. Shutin
			30 - 30. Strong blow throughout. 40' of
			mud with oil specks. 60' slightly oil cut
			mud. ISIP 192#/30 min. FSIP 192#/30 min.
			IFP 38# FFP 80#
			RTD 4297' D & A Ran gamma ray, neutron,
			focused log.


RECEIVED
STATE CORPORATION COMMISSION

JUL 7 1965
7-7-65
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
SS
COUNTY OF BARTON

The undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

ASPEN DRILLING CO.


Jack M. Dunham, Tool Pusher