

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-185-20784-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 26 Twp. 25 Rge. 15 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C NW of SE


Lease Owner Davis & Reed
Lease Name Anderson Well No. 1
Office Address Fourth Financial Center Suite 645
Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
dry hole

Date Well completed Dec. 11 1977
Application for plugging filed Dec. 11 1977
Application for plugging approved Dec. 11 1977
Plugging commenced 8:30 Dec. 11 1977
Plugging completed 9:30 Dec. 11 1977
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? ~~Bill Owen~~ yes

Name of Conservation Agent who supervised plugging of this well Bill Owen
Producing formation Depth to top Bottom Total Depth of Well 4335'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug 550' W/40 SX 50/50 Pozmix, 2% Gel.
Middle Plug 300' W/25 SX " " "
Top Plug 40' W/1/2 sack hulls, 12 sx Pozmix
3 sx in rat hole

RECEIVED
STATE CORPORATION COMMISSION 12-14-77

(If additional description is necessary, use back of this sheet)
Name of Plugging Contractor

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
Wayne Dobbs (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed and that the same are true and correct. So help me God.

(Signature) Wayne Dobbs
Wayne Dobbs

SUBSCRIBED AND SWORN TO before me this 12th day of December, 19 77

Bessie M. DeWerff
Bessie DeWerff Notary Public.

My commission expires 5-20-81

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81

DRILLERS WELL LOG 15-185-20784-0000

L. D. DRILLING COMPANY - CONTRACTOR

DAVIS & REED - OPERATOR

ANDERSON # 1
C NW of SE 26-25-15W
STAFFORD, COUNTY

ELEV. 2010 K B
T. D. 4335

CASING

8 5/8" set at 299'

COMMENCED: 11-30-77
COMPLETED: 12-11-77

CEMENT

235 Sx. 60/40 Pozmix, 2% Gel, 3% CC

FORMATION

Sand
Shale & Red Bed
Anhy.
Shale & Shells
Lime & Shale
Shale
Lime & Shale
Cong.

DEPTH

0 - 275
275 - 954
954 - 973
973 - 1700
1700 - 3653
3653 - 3657
3657 - 4102
4102 - 4335

TOPS

Heebner
Douglas
Brn. Lime
Lansing
Base K/C
Cherokee
Miss.
Kinderhook Cht.
T.D.

3653
3693
3795
3838
4102
4244
4262
4323
4335

AFFIDAVIT

State of Kansas County of Barton

I, Wayne Dobbs of the L. D. Drilling Company

being first duly sworn on oath, State: That I have knowledge of the facts statements and matters herein contained and that the same are true and correct.

Wayne Dobbs
Wayne Dobbs

Subscribed and sworn to before me on this 12th day of December 1977

My commission expires: 5-20-81

Bessie M. DeWerff
Bessie M. DeWerff Notary Public

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81

RECEIVED
STATE CORPORATION COMMISSION

DEC 14 1977

CONSERVATION DIVISION
Wichita, Kansas